



भेरीगंगा नगरपालिका
नगर कार्यपालिकाको कार्यालय
छिन्चु, सुर्खेत
कर्णाली प्रदेश, नेपाल

Fax ०८३- ५४०११०
Phone ०८३- ५४०१५४

प.सं. :- ०७९/०८०

च नं: २२४२



मिति : २०७९/१२/२८

विषय :- शाखा भवन र वडा नं.१० को सडक निर्माणको लागि दररेट पेश गर्ने सूचना ।

श्री सम्बन्धित सरोकारवाला सबै ।

प्रस्तुत बिषयमा यस नगरपालिका आ.व.२०७९/०८० को तपशिल बमोजिमको भवन निर्माण र सडक ग्राभेल निर्माण कार्य गर्नुपर्ने भएको हुदा यस कार्यालय बाट सूचना प्रकाशित भएको मितिले ७ दिन भित्र (मिति २०८०/०१/०४ गते दिनको ५:०० बजे) सम्मा ईच्छुक निर्माण व्यवसायी तथा फर्महरूले भेरीगंगा नगरपालिकाको वेवसाईट www.bherigangamun.gov.np मा यसै पत्र साथ राखिएको BOQ भरि सुचिकृत भई आफ्नो दररेट सिलबन्दी गरि नगरपालिकाको कार्यालयमा पेश गर्नुहुन सम्बन्धित सरोकारवालामा यो सूचना प्रकाशित गरिएको छ ।

नोट: म्याद नाघी पेश भएका दर रेट मान्य हुने छैन ।

क्र.स.	कार्यक्रमको नाम	अधिकतम रकम रु.	कैफियत
१.	वडा नं.१० को सडक कटिग र ग्राभेल	रु.९,९९,७५१.६८	भ्याटसहित
२.	कृषि बिकास शाखा को मिनी ल्याब निर्माण र पशुपन्छी बिकास शाखाको कोठा निर्माण	रु.८,०९,८५३.६८	भ्याटसहित

(Signature)

(Signature)

कृष्ण प्रसाद पोखरेल
प्रमुख प्रशासकीय अधिकृत

प्रमुख प्रशासकीय अधिकृत

Bheriganga municipality
Office of the municipal executive
Chinchu- Surkhet
Karnali, province, nepal
BILL OF QUANTITY (BOQ)

Name of project:-kirshi bikash sakha ra vetenary sakha kotha nirman

Location: Bheriganga Municipality

Word No: 12

Office Code no:-
F.Y:2079/080

S.N.	Description of Works	Unit	Quantity	Rate (NRs.)		Amounts (NRs.)	Remarks
				In Figure	In Words		
A	kirshi bikash sakha kotha nirman						
1	Earth work in excavation BMS soil	cum	14.02				
2	Stone solling without sand	cum	4.95				
3	PCC 1:2:4 crushed aggregate	cum	2.89				
4	Stone masonry wall with 1:6 ratio of cement motar	cum	6.78				
5	M.S black pipe tubler Light A-class truss fittings roof all complete work	kg	441.61				
6	CGI colour sheet for roofing work as 26 gauge	sqm	39.06				
7	CGI plain sheet for ridge 26 gauge	rm	9.30				
8	Brick masonry work with (1:4) cement sand mortar	cum	10.02				
9	Sal wood chaukhat with all complete works	cum	0.25				
10	32mm readymade door as fitting and fixing with all complete work	sqm ft.	53.50				
11	Making and fixing pannel shutter as fitting fixing window with 1.5" sal frame 4mm glazed	sqm	2.96				
B	vetenary sakha kotha nirman						
1	First class chiminey brick masonry work in 1:4 C/S mortar in ground floor	cum	6.05				
2	sal wood work for chaukhat with all complete	cum	0.16				
3	32mm readymade door two way teak ply added modling with listy	sqm ft.	38.74				
4	1.5"mm thick sal wood frame with 4mm thick fully glazed shutter fixing work with all complete works	sqm	3.78				
5	ms grill with painting fixing all complete work	kg	72.58				
6	12mm plaster 1:4 cement sand mortar	sqm	108.50				
7	50mm or 2" thick pcc (1:2:4) work in floor with crushed aggregate all complete work	cum	4.00				
8	3mm thick neat cement punning works	sqm	50.00				
9	two coat enamenl painting work over primer coat wooden surface	sqm	3.67				
			Sub-total Cost NRs.				
			Vat @13%				
			Grand Total Amount NRs.				

Total Amount in words:-

Name of Form/Suppliers:-
 Firm Registration No:-
 PAN/VAT Reg. No.:-

Singnature & Stamp

Proprietor's Name:-
 Address:-