



प.सं. :- २०८२/०८३

च.न. : १८०३

भेरीगंगा नगरपालिका नगर कार्यपालिकाको कार्यालय

छिन्चु, सुर्खेत
कर्णाली प्रदेश, नेपाल

२०७३



☎ ०८३-२४०१२४, २४०१११

E-mail: info@bherigangamun.gov.np
: ito.bherigangamun@gmail.com

Website: bherigangamun.gov.np

☎ Toll Free No. : 18105000311

मिति : २०८३/०२/०६

विषय: दर रेट पेश गर्नेबारे सूचना ।


श्री सम्बन्धित सरोकारवाला सबै ।

प्रस्तुत विषयमा यस भेरीगंगा नगरपालिकाको तपसिलमा उल्लेखित कार्य गर्नुपर्ने देखिएको हुदा यस कार्यालय बाट सूचना प्रकाशित भएको मितिले ७ (सात) दिन भित्र (मिति २०८३/०२/१२ गते दिनको ५:०० बजे सम्ममा) इच्छुक सप्लायर्स/फर्महरूले भेरीगंगा नगरपालिकाको वेबसाइट www.bherigangamun.gov.np मा यसै सूचना साथ राखिएको BOQ भरि सुचिकृत भई आफ्नो दररेट सिलबन्दी गरि यस नगरपालिकाको कार्यालयमा पेश गर्नुहुन सम्बन्धित सरोकारवालामा यो सूचना प्रकाशित गरिएको छ ।

नोट: म्याद नाघी पेश भएका प्रस्ताव मान्य हुने छैन ।

क्र. सं.	कार्यक्रमको नाम	अधिकतम रकम रु. (म्याट सहित)	आवश्यक कागजात
१	सामाखोरिया देखि ६ नम्बर वडा जोड्ने सडक मर्मत	रु. ४,६९,१६४.३१	१. आ.व.२०८१/०८२ को करचुक्ता प्रमाणपत्रको प्रतिलिपि २. फर्म/सप्लायर्स दर्ता संग सम्बन्धित सम्पूर्ण कागजातहरूको प्रतिलिपि ३. सुचिकृत भएको रसिद तथा प्रमाणको प्रतिलिपि
२	छिन्चु जाजरकोट सडकदेखि मैनतडा जाने सडक स्तारुन्ती	रु. ४,६९,२१५.८२	
३	विकासपुर मानकोटी टोल देखि शान्तिपुर जाने सडक स्तारुन्ती	रु. ४,६९,१९३.१०	
४	वडा कार्यालय जाने सडक स्तारुन्ती	रु. ४,६९,२०५.२८	
५	राताचौरदेखि रामघाट झुलुंगे पुल जाने सडक मर्मत	रु. ४,६८,५६१.०४	
६	गणेशपुर चोक देखि सिस्नेखुटि जाने सडक स्तारुन्ती	रु. ४,६९,१५८.१	
७	तल्लो आपखोलि वडा कार्यालय सडक स्तारुन्ती	रु. ४,६९,२९८.७६	


इन्जिनियर


हरि बहादुर खत्री

प्रमुख प्रशासकीय अधिकृत
हरि बहादुर खत्री
प्रमुख प्रशासकीय अधिकृत

“समृद्ध भेरीगंगा-सुखी भेरीगंगावासी”



Bheriganga Municipality
Office Of the Municipal Executive
Chhinchu, Surkhet
Karnali Province, Nepal

Bill of Quantities

1. Road Agency : Bheriganga Municipality
2. Agency Chief : Hari Bahadur Khatri
3. Road Name : Bikasapur Mankoti Tol Dekhi Shantipur Jane sadak Istaronnati
4. Budget Heading : 337310113 (26421)
5. Vehicle Traffic : 80 Nos. per day

6. Road Condition : Fair
7. Road Type : Gravel
8. Total Length of Road : 3.5 Km

9. Length of road under maintenance: 0.7 Km
10. Width of Road : 6 M

S.N.	Description	Unit	Quantity	Rate (In Figure)	Rate in Words	Amount	Remarks
1.0	Earthwork in excavation in medium type soils in foundation for drain repairBy mechanical at (Chainage 0+020 to 0+050, 1+150 to 0+200 , 0+560 to 0+570 , 1+160 to 1+174) including 10m hauling distance and 1.8 m. lift all complete in approval of site engineer.	M3	63.23				
2.0	Earthwork in excavation in medium type soils in foundation for drain repair by Manually at (Chainage 0+020 to 0+050, 1+150 to 0+200 , 0+560 to 0+570 , 1+160 to 1+174) including 10m hauling distance and 1.8 m. lift all complete in approval of site engineer.	M3	3.20				
3.0	Supplying and soling stone in proper line and level without sand filling at (Chainage 0+020 to 0+050, 1+150 to 0+200 , 0+560 to 0+570 , 1+160 to 1+174)	M3	6.77				
4.0	PCC work with(1:2:4) crushed aggregate at (Chainage 0+020 to 0+050, 1+150 to 0+200 , 0+560 to 0+570 , 1+160 to 1+174)	M3	6.59				
5.0	Providing and laying plumb Concrete(Boulder mixed concrete)as per drawing and specification 60% M15 concrete and 40% boulders/stones Manually at (Chainage 0+020 to 0+050, 1+150 to 0+200 , 0+560 to 0+570 , 1+160 to 1+178)	M3	13.48				
6.0	Formwork, shuttering, centering with 19mm thick waterproof ply board and steel post for all works necessary propping, scaffolding, staging, supporting inclusive of wedging and cutting holes for utilization till the support if fully unyielding nett all complete as per approved drawing, Specification and instruction of site engineer.	M2	37.07				
7.0	Rubble Stone Masonary work with (1:6) C/S at (Chainage 0+020 to 0+050, 1+150 to 0+200 , 0+560 to 0+570 , 1+160 to 1+174)	M3	16.88				
8.0	Hoading Board size 1.2*0.9 m2 size flex	N0.	1.00				
				Sub Total			
				VAT @ 13%			
				Grand Total with VAT			

[Signature]
इन्जिनियर

[Signature]
2080/08
F/Y 2080/08
Ward No. 49
प्रमुख प्रशासकीय अधिकारी