



प.सं. :- २०८२/०८३

च.नं. १६१५

भेरीगंगा नगरपालिका नगर कार्यपालिकाको कार्यालय

छिन्चु, सुर्खेत
कर्णाली प्रदेश, नेपाल
२०७३
भेरीगंगा नगर
नगर कार्यपालिकाको कार्यालय
सुर्खेत, नेपाल
कर्णाली प्रदेश, नेपाल
२०७३



☎ ०८३-४४०१४४, ४४०१११

E-mail: info@bherigangamun.gov.np

:ito.bherigangamun@gmail.com

Website: bherigangamun.gov.np

☎ Toll Free No. : 18105000311

मिति : २०८२/१०/०९

विषय: दर रेट पेश गर्नेबारे सूचना ।

श्री सम्बन्धित सरोकारवाला सबै ।

प्रस्तुत बिषयमा यस भेरीगंगा नगरपालिकाको तपसिलमा उल्लेखित कार्य गर्नुपर्ने देखिएको हुदा यस कार्यालय बाट सूचना प्रकाशित भएको मितिले ७ दिन भित्र (मिति २०८२/१०/१५ गते दिनको ५:०० बजे सम्ममा) इच्छुक सप्लायर्स/फर्महरुले भेरीगंगा नगरपालिकाको वेबसाइट www.bherigangamun.gov.np मा यसै सूचना साथ राखिएको BOQ भरि सुचिकृत भई आफ्नो दररेट सिलबन्दी गरि यस नगरपालिकाको कार्यालयमा पेश गर्नुहुन सम्बन्धित सरोकारवालामा यो सूचना प्रकाशित गरिएको छ ।

नोट: म्याद नाघी पेश भएका प्रस्ताव मान्य हुने छैन ।

क्र. सं.	कार्यक्रमको नाम	अधिकतम रकम रु. (भ्याट सहित)	आवश्यक कागजात
२.	सिसौघारी धमिनी टोल झिगेनारा कल्भर्ट निर्माण, भेरीगंगा-१० ।	रु. ९,९९,८३४.४७/-	४. आ.व. २०८१/०८२ को करचुक्ता प्रमाणपत्रको प्रतिलिपि ५. फर्म/सप्लायर्स दर्ता संग सम्बन्धित सम्पूर्ण कागजातहरुको प्रतिलिपि ६. सुचिकृत भएको रसिद तथा प्रमाणको प्रतिलिपि

मान बहादुर ठाडा

प्रमुख प्रशासकिय अधिकृत

प्रमुख प्रशासकिय अधिकृत

“समृद्ध भेरीगंगा-सुखी भेरीगंगावासी”



Bheriganga Municipality
Office Of Municipal Executives
Chhinchu, Surkhet
Karnali Province

BILL OF QUANTITIES (BOQ)

Name of Project :- Sisaughari Dhamini Tol Jhingenara Culvert Nirman
Location : Bheriganga Municipality 10, Surkhet

FY:2082/083

S.N.	Description of Items	Unit	Quantity	Unit Rate (NRs.)		Amount (NRs.)	Remarks
				In Figures	In Words		
1	Provision for Lab Test as per instruction of site incharge Earthwork Excavations in Hard soil as per drawing and technical specification, including removal of stumps and other deleterious matter with all lifts and lead as per drawing and instruction of the engineer.	PS	1.00	5000.00	Five Thousand Only	5000	
2		M3	12.10				
3	Earthwork Excavation in Cutting, Excavation in Hard Rock (blasting prohibited), Roadway Excavation in hard rock with rock breakers, including breaking rock, lifts and lead for disposal as per Drawing and Technical Specifications, Mechanical method, lead upto 30 m	M3	18.48				
4	Providing and laying of hand pack Stone soling with 150 to 300 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	M3	5.50				
5	Providing and laying of Plain Cement Concrete M 15 (or 1:2:4 for nominal mix) in Foundation complete including formworks as per Drawing and Technical Specifications.	M3	3.30				
6	Providing and laying plum concrete (Boulder mixed concrete) as per drawing and specification 60 % M15 concrete and 40 % boulders/stones using Mechanical Aids including formwork	M3	51.12				
7	Providing and laying of Plain/Reinforced Cement Concrete in Foundation complete including formwork as per Drawing and Technical Specifications., RCC Grade M 20 including formwork	M3	21.48				
8	Providing and laying,fitting and placing un-coated mild steel/HYSD reinforcement complete in sub-structure as per drawing and technical apcification	Kg	1730.25				
9	Construction of subgrade by Providing and laying sub-grade and earthen shoulders with approved Material obtained from borrow pits with all lifts & leads as per Drawing and Technical Specifications. (Capping layer-with granular material)	M3	60.00				



Bheriganga Municipality
Office Of Municipal Executives
Chhinchu, Surkhet
Karnali Province

BILL OF QUANTITIES (BOQ)

Name of Project :- Sisaughari Dhamini Tol Jhingenara Culvert Nirman
Location : Bheriganga Municipality 10, Surkhet



FY:2082/083

S.N.	Description of Items	Unit	Quantity	Unit Rate (NRs.)		Amount (NRs.)	Remarks
				In Figures	In Words		
10	Information board in flex	No.	1.00				
TOTAL AMOUNT WITHOUT VAT							
VAT (@13%)							
TOTAL AMOUNT WITH VAT							
TOTAL AMOUNT WITH VAT IN WORDS:							

Name of Firm:
Name of contractor/Representative:
Address:
Date:
Seal of Firm:
Contact No. :