भेरीगंगा नगरपालिका
नगर कार्यपालिकाको कार्यालय
छिन्चु, सुर्खेत
कर्णाली प्रदेश, नेपाल
२०७३

☎०८३-५४०१५४, ५४०१११
E-mail:info@bherigangamun.gov.np
:ito.bherigangamun@gmail.com
Website: bherigangamun.gov.np
☎ Toll Free No. : 18105000311

प.सं. :- २०८२/०८३
च.नं.:१८९३

मिति : २०८३/०२/०६

विषय: दर रेट पेश गर्नेबारे सूचना।

श्री सम्बन्धित सरोकारवाला सबै।

प्रस्तुत बिषयमा यस भेरीगंगा नगरपालिकाको तपसिलमा उल्लेखित कार्य गर्नुपर्ने देखिएको हुदा यस कार्यालय बाट सूचना प्रकाशित भएको मितिले ७ (सात) दिन भित्र (मिति २०८३/०२/१२ गते दिनको ५:०० बजे सम्ममा) इच्छुक सप्लायर्स/फर्महरुले भेरीगंगा नगरपालिकाको वेबसाइट www.bherigangamun.gov.np मा यसै सूचना साथ राखिएको BOQ भरि सुचिकृत भई आफ्नो दररेट सिलबन्दी गरि यस नगरपालिकाको कार्यालयमा पेश गर्नुहुन सम्बन्धित सरोकारवालामा यो सूचना प्रकाशित गरिएको छ।

नोट: म्याद नाघी पेश भएका प्रस्ताव मान्य हुने छैन।

क्र. सं.	कार्यक्रमको नाम	अधिकतम रकम रु. (भ्याट सहित)	आवश्यक कागजात
१	सामाखोरिया देखि ६ नम्बर वडा जोड्ने सडक मर्मत	रु. ४,६९,१६४.३१	१. आ.व.२०८१/०८२ को करचुक्ता प्रमाणपत्रको प्रतिलिपि २. फर्म/सप्लायर्स दर्ता संग सम्बन्धित सम्पूर्ण कागजातहरुको प्रतिलिपि ३. सुचिकृत भएको रसिद तथा प्रमाणको प्रतिलिपि
२	छिन्चु जाजरकोट सडकदेखि मैनतडा जाने सडक स्तारुन्नती	रु. ४,६९,२१५.८२	
३	विकासपुर मानकोटी टोल देखि शान्तिपुर जाने सडक स्तारुन्नती	रु. ४,६९,१९३.१०	
४	वडा कार्यालय जाने सडक स्तारुन्नती	रु. ४,६९,२०५.२८	
५	राताचौरदेखि रामघाट झुलुंगे पुल जाने सडक मर्मत	रु. ४,६८,५६१.०४	
६	गणेशपुर चोक देखि सिस्नेखुटि जाने सडक स्तारुन्नती	रु. ४,६९,१५८.१	
७	तल्लो आपखोलि वडा कार्यलय सडक स्तारुन्नती	रु. ४,६९,२९८.७६	

इन्जिनियर

हरि बहादुर खत्री
प्रमुख प्रशासकिय अधिकृत
हरि बहादुर खत्री
प्रमुख प्रशासकीय अधिकृत

Bheriganga Municipality
Office of Municipal Executive
Bill of Qunatities

1. Road Agency : Bheriganga Municipality
2. Agency Chief :Hari Bahadur Khatri
3 Road Name :Samakhoriya dekhi 6 no warda jodne sadak marmat
4. Budget Heading : 337310113 (26421)
5. Vehicle Traffic : 200 Nos. per day
6. Road Condition : FAIR
7. Road Type : Earthen
8. Total Length of Road : 5 Km
9. Length of road Under maintenance: 0.1 Km
10. Width of Road : 5 M

Item No.	Description	Unit	Quantity	Rate (In Figure)	Rate (In words)	Amount	Remarks
B	**Civil works**						
	Earthwork Excavation in Cutting., Roadway Excavation in all types of Soil by Mechanical Means ., Road way Excavation in all types of soil as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer.	Cu m	90.00				
3	Gabion Structure for Retaining Earth, Mesh wire- 10 Swg(0.0615 kg/m), Selvedge Wire 8 Swg (0.1057 kg/m), binding wire 12 Swg (0.0409 kg/m) Hexagonal mesh Type 100 mm X 120 mm,, Box size 1.5 X 1 X 1 m (9 sqm)	Nos	40.00				
4	Gabion Structure for Retaining Earth, Mesh wire- 10 Swg(0.0615 kg/m), Selvedge Wire 8 Swg (0.1057 kg/m), binding wire 12 Swg (0.0409 kg/m) Hexagonal mesh Type 100 mm X 120 mm,, Box size 2 X 1 X 1 m (11 sqm)	Nos	29.00				
5	Providing and installation of project signboards with size of 1.8 x 1.2 m as per specification and instruction of engineer.	job	1.00				
				Sub total			
			VAT @ 13%				
			Grand Total VAT				
		Total With vat and provisional					

CamScanner